

WATER SERVICE - MICHIGAN BASEMENT PENETRATION

 OPEN CUT INSTALLATION - TRACER WIRE TO BE COPPERHEAD, 12 AWG, 452 POUNDS BREAK LOAD
DIRECTIONAL BORING - TRACER WIRE TO BE COPPERHEAD, 12 AWG, 1,150 POUNDS BREAK LOAD,

2 WIRES REQUIRED