

-USE 1/4" ROLLED BUTYL MASTIC ROPE BETWEEN CASTING AND RING, ONE ALONG INSIDE AND OUTSIDE EDGES WHEN POSSIBLE. FOR FINE ADJUSTMENT, A NON-SHRINK RAPID SETTING MORTAR, SPEED CRETE REDLINE OR SIMILAR APPROVED MATERIAL CAN BE USED, MAXIMUM OF 2" THICKNESS. NO SHIMS, BRICK OR CONCRETE UNDER CASTING

MAXIMUM 12" OF ADJUSTMENT, 2 OR FEWER RINGS. 2" AND THICKER PRE-CAST RINGS ONLY. BRICK STRUCTURE - IF THE TOP OF THE STRUCTURE NEEDS REPAIRED OR REBUILT BEYOND THE 12" MAXIMUM, THE ENGINEERING DEPARTMENT WILL DETERMINE THE ACCEPTABLE REPAIR UP TO AND INCLUDING REPLACEMENT WITH A PRE-CAST CONCRETE STRUCTURE

## **CHIMNEY RECONSTRUCTION**

NOT TO SCALE

## The City Of Goshen

Department of Public Works & Safety Office of Engineering

204 East Jefferson, Suite 1 Street, Goshen, Indiana 46528 Phone: 574-534-2201 Fax: 574-533-8626 Web: goshenindiana.org

Date Appro	Date Approved By The City Of Goshen Board Of Public Works & Safety and Approved Revisions				
03/27/2025	07/24/2025				

CITY OF GOSHEN, INDIANA STANDARD DETAIL

7	Drafted By:	Approved By:			
١	J. Hoffman	D. Sailor, P.E			
- 1	Drawing Number:				
	SW-	109			